

Best Available Copy

**PRV**

PATENT- OCH REGISTRERINGSVERKET  
Patentavdelningen

PCT/SE04/01068

**Intyg  
Certificate**

Härmed intygas att bifogade kopior överensstämmer med de handlingar som ursprungligen ingivits till Patent- och registreringsverket i nedannämnda ansökan.

This is to certify that the annexed is a true copy of the documents as originally filed with the Patent- and Registration Office in connection with the following patent application.



(71) Sökande                      Anders Furuskär Stockholm SE,  
Applicant                      Arne Simonsson Gammelstad SE

(81) Designerade stater      AP: all, AE, AG, AL, AM, AT, AU, AZ, BA, BB,  
Designated states              BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ,  
   DE, DK, DM, DZ, EC, EE, EG, ES, FI, GB, GD,  
   GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE,  
   KG, KP, KR, KZ, LC, LI, LK, LR, LS, LT, LU,  
   LV, MA, MD, MG, MK, MN, MW, MX, MZ, NI, NO,  
   NZ, OM, PG, PH, PL, PT, RO, RU, SC, SD, SE,  
   SG, SK, SL, SY, TJ, TM, TN, TR, TT, TZ, UA,  
   UG, US, UZ, VC, VN, YU, ZA, ZM, ZW

(21) Patentansökningsnummer      PCT SE03/01965  
Patent application number

(86) Ingivningsdatum                      2003-12-17  
Date of filing

Stockholm, 2004-07-26

REC'D 09 AUG 2004

WIPO

PCT

För Patent- och registreringsverket  
For the Patent- and Registration Office

Görel Gustafsson

Avgift  
Fee

**PRIORITY DOCUMENT**  
SUBMITTED OR TRANSMITTED IN  
COMPLIANCE WITH  
RULE 17.1(a) OR (b)

**PATENT- OCH  
REGISTRERINGSVERKET  
SWEDEN**

Postadress/Adress  
Box 5055  
S-102 42 STOCKHOLM

Telefon/Phone  
+46 8 782 25 00  
Vx 08-782 25 00

Telex  
17978  
PATOREG S

Telefax  
+46 8 666 02 86  
08-666 02 86

## PCT REQUEST

1/4

P06487PC00

Original (for SUBMISSION) - printed on 16.12.2003 10:00:07 AM

0	For receiving Office use only	
0-1	International Application No.	PCT/ SE 03 / 01965
0-2	International Filing Date	17-12-2003
0-3	Name of receiving Office and "PCT International Application"	The Swedish Patent Office PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.92 (updated 01.07.2003)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	Swedish Patent Office (RO/SE)
0-7	Applicant's or agent's file reference	P06487PC00
I	Title of invention	A METHOD IN MULTI ACCESS SYSTEM
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	Telefonaktiebolaget LM-Ericsson (publ.)
II-5	Address:	S-126 25 STOCKHOLM Sweden
II-6	State of nationality	SE
II-7	State of residence	SE
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	FURUSKÄR, Anders
III-1-5	Address:	Ångströmsgatan 5 S-112 69 STOCKHOLM Sweden
III-1-6	State of nationality	SE
III-1-7	State of residence	SE

## PCT REQUEST

P06487PC00

Original (for SUBMISSION) - printed on 16.12.2003 10:00:07 AM

III-2	Applicant and/or inventor	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	SIMONSSON, Arne
III-2-5	Address:	Sandåkersvägen 25 S-954 33 GAMMELSTAD Sweden
III-2-6	State of nationality	SE
III-2-7	State of residence	SE
IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	DR LUDWIG BRANN PATENTBYRÅ AB
IV-1-2	Address:	Box 17192 S-104 62 STOCKHOLM Sweden
IV-1-3	Telephone No.	+46 18 568900
IV-1-4	Facsimile No.	+46 18 568939
IV-1-5	e-mail	brann@brann.se
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AP: GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT EP: AT BE BG CH&LI CY CZ DE DK EE ES FI FR GB GR HU IE IT LU MC NL PT RO SE SI SK TR and any other State which is a Contracting State of the European Patent Convention and of the PCT OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT

## PCT REQUEST

Original (for SUBMISSION) - printed on 16.12.2003 10:00:07 AM


P06487PC00

V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	AE AG AL AM AT (patent and utility model) AU AZ BA BB BG BR BY BZ CA CH&LI CN CO CR CU CZ (patent and utility model) DE (patent and utility model) DK (patent and utility model) DM DZ EC EE (patent and utility model) EG ES FI (patent and utility model) GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NI NO NZ OM PG PH PL PT (patent and utility model) RO RU SC SD SE SG SK (patent and utility model) SL SY TJ TM TN TR TT TZ UA UG US UZ VC VN YU ZA ZM ZW	
V-5	Precautionary Designation Statement  In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	Exclusion(s) from precautionary designations	NONE	
VI	Priority claim	NONE	
VII-1	International Searching Authority Chosen	Swedish Patent Office (ISA/SE)	
VIII	Declarations	Number of declarations	
VIII-1	Declaration as to the identity of the inventor	-	
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	-	
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-	
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-	
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-	

## PCT REQUEST

P06487PC00

Original (for SUBMISSION) - printed on 16.12.2003 10:00:07 AM

IX	Check list	number of sheets	electronic file(s) attached
IX-1	Request (including declaration sheets)	4 ✓	-
IX-2	Description	14 ✓	-
IX-3	Claims	7 ✓	-
IX-4	Abstract	1 ✓	EZABST00.TXT
IX-5	Drawings	4 ✓	-
IX-7	TOTAL	30	
IX-8	Accompanying items	paper document(s) attached	electronic file(s) attached
	Fee calculation sheet	✓	-
IX-17	PCT-EASY diskette	-	Diskette
IX-19	Figure of the drawings which should accompany the abstract	2	
IX-20	Language of filing of the international application	English	
X-1	Signature of applicant, agent or common representative		
X-1-1	Name	DR LUDWIG BRANN PATENTBYRÅ AB	
X-1-2	Name of signatory	Ellen Stavbom	
X-1-3	Capacity	Patent Attorney	

## FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	17-12-2003
10-2	Drawings:	X
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/SE
10-6	Transmittal of search copy delayed until search fee is paid	

## FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

## PCT (ANNEX - FEE CALCULATION SHEET)

P06487PC00

Original (for SUBMISSION) - printed on 16.12.2003 10:00:07 AM

(This sheet is not part of and does not count as a sheet of the international application)

0	For receiving Office use only		
0-1	International Application No.	PCT/ SE 03 / 01965	
0-2	Date stamp of the receiving Office	17-12-2003	
0-4	Form - PCT/RO/101 (Annex) PCT Fee Calculation Sheet Prepared using	PCT-EASY Version 2.92 (updated 01.07.2003)	
0-9	Applicant's or agent's file reference	P06487PC00	
2	Applicant	Telefonaktiebolaget LM Ericsson (publ.), et al.	
12	Calculation of prescribed fees	fee amount/multiplier	Total amounts (SEK)
12-1	Transmittal fee T	⇒	1 200 1200
12-2-1	Search fee S	⇒	8 720 8720
12-2-2	International search to be carried out by	SE	
12-3	International fee		
	Basic fee		
	(first 30 sheets) b1	3 940	
12-4	Remaining sheets	0	
12-5	Additional amount (X)	90	
12-6	Total additional amount b2	0	
12-7	b1 + b2 = B	3 940	
12-8	Designation fees		
	Number of designations contained in international application	98	
12-9	Number of designation fees payable (maximum 5)	5	
12-10	Amount of designation fee (X)	850	
12-11	Total designation fees D	4 250	
12-12	PCT-EASY fee reduction R	-1 210	
12-13	Total International fee (B+D-R) I	⇒	6 980 6980
12-17	TOTAL FEES PAYABLE (T+S+I+P)	⇒	16 900 16900
12-19	Mode of payment	cheque	

## VALIDATION LOG AND REMARKS

13-2-3	Validation messages Names	Green? Applicant 1.: Name should preferably be entered in capital letters. Please verify.
		Yellow Applicant 1.: Street address missing
		Green? Applicant 1.: Telephone No. missing

A method in a multi access system

## TECHNICAL FIELD OF THE INVENTION

- 5 The present invention relates to a method, a system, a terminal and a computer program product for selecting radio access system in a multi access system handling packet data services where a terminal can communicate with at least two different types of access systems.

~~TO BACKGROUND OF THE INVENTION AND RELATED ART~~

Several multi-access scenarios will exist in the near future, for example UMTS (Universal Mobile Telecommunication System)/GSM (Global System for Mobile communication) and UMTS/WLAN (Wireless Local Area Network). In many cases, the same end-user service can be carried by more than one of the included accesses.

- 15 For example, best effort packet data can be carried by both UMTS and WLAN. A selection of which access to use must thus be done.

In the prior art, it has been observed that the accesses are, on a by call or session basis, not equally efficient for different types of end user services. Consequently, to increase the common multi-access capacity, it has been proposed to allocate calls or sessions of a service to the access by which the service is most efficiently handled. This is described in patent application nr: PCT/SE03/00611.

In Alcatel, "Simultaneous Access", S2-030215, 3GPP TSG-SA WG meeting #29, 3GPP, it is discussed to enable simultaneous packet switched associations over WLAN and cellular (GPRS (General Packet Radio Service)). That is to establish and maintain two connection paths enabling packet transmission through both accesses without prior signaling.

There are two widely discussed ways to combine the existing cellular and WLAN structures, tight interworking and loose interworking. This is described in "WLAN-

GPRS Integration for Next-Generation Mobile Data Networks” by Apostolis et al.  
IEEE Wireless Communication, October 2002.

In ”Stand-Alone Data-Cells for UMTS”, Tdoc FEW-0032/01, 3GPP Future Evolution  
Workshop, October 2001 Helsinki, Source: Nortel Networks, an additional suggestion,  
5 WLAN integrated in UTRAN, is described.

In the above scenarios, there is a possibility to maintain associations through both  
cellular and WLAN radio access, as discussed in ”Simultaneous Access”. The protocol  
level where the association shall be maintained will be dependent on the splitting point  
on the network side, i.e. the ”last” common node for the different systems. Examples

10 are:

- For WLAN integrated in UTRAN (UMTS Terrestrial Radio Access Network) the  
splitting point for WLAN/UMTS is in the RNC (Radio Network Controller). Two  
associations are then maintained on RNC-level.

- For tight interworking the splitting point is in SGSN (Serving GPRS Support Node).  
15 Two associations are then maintained on IP-level. That means two IP-addresses and  
multihoming, see ”Simultaneous Access”.

- For loose interworking the splitting point is in an IP-router. Two associations are  
then maintained on IP-level as for tight interwork.

20 For all scenarios there is also a splitting point in the user terminals, i.e. the terminals  
need to be able to communicate through the different access systems and the terminal  
has to choose, or be instructed to choose, one of the systems.

End user services are partly characterized by a set of traffic characteristics, including  
25 packet size statistics. In ”On the Need for Efficiency in the 802.11 QoS Solution” by  
M. Sherman, IEEE 802.11-01/045, January 2001, it is disclosed that the spectrum  
efficiency of the WLAN (IEEE 802.11) depends on the packet size. Small packets are  
inefficiently handled, especially for the higher order modulation schemes.



## SUMMARY

An object of the present invention is to provide an effective multi access system.

5

This object is achieved in a method according to claim 1, a system according to claim 9, a terminal according to Claim 18 and a computer program product according to claims 27 and 28.

10

The selection of access is according to the invention based on packet characteristics and a new selection of access is made for each packet to be transmitted. Hereby the best access is selected for each packet and the efficiency of the system is increased.

15

Suitably the load in the different access systems is considered together with the packet characteristics when selecting one of the access systems.

20

In one preferred embodiment the determined packet characteristics is packet size and suitably the determined packet size is compared with at least one packet size threshold which is defined in the multi access system as a border value of the packet size where a larger packet size suitably is transferred in one access system and a smaller packet size suitably is transferred in another access system for achieving the best transferring efficiency.

25

Further suitable embodiments are described in the dependent claims.

## BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 is a schematic view of the inventive parts in a splitting point in a multi access system.

30

Figure 2 is a flow chart of the inventive method.

Figure 3 is a flow chart of one embodiment of the invention.

Figure 4 is a diagram showing throughput in two different accesses in relation to packet size.

Figure 5 is a diagram showing throughput in two other accesses in relation to packet size.

5

## DETAILED DESCRIPTION OF THE EMBODIMENTS

According to the invention several (at least two) radio accesses are available and interfaced by user terminals in the system. In a multi-access network for packet data

10 ~~according to the invention the selection of radio access shall be based on individual~~  
packet level, rather than on service level (which roughly corresponds to expected packet statistics). Each service/connection is associated to and utilizes several accesses and each packet is sent on the most efficient access. One packet characteristic that can  
15 inter-arrival-time, i.e. the time between subsequent packets in a data flow, since delay in cellular systems is dependent on the packet inter-arrival-time because of set up times.

Examples of other packet individual characteristics that has different performance on  
20 different accesses and that could differ between packets within the same flow are PER(Packet Error Rate)-requirements, BER(Bit Error Rate)-requirements and delay requirements. Packets with different delay and error rate requirements often appear in multimedia flows, e.g. during a net meeting session with mixed voice, video and slide  
25 show data. Different access technologies may perform differently well for different packet or bit error rate requirements. For example, due to updating the transmission power 1500 times per second, WCDMA efficiently supports very low bit and packet error rates. In GSM on the other hand, the power is updated only 2 times per second, and low packet or bit error rates less efficiently supported.

30 The same is true for different delay requirements. For example, GSM/EDGE offers high capacity provided that a relatively large number of retransmission of every packet

is allowed. If, in order to reduce delay, no retransmissions are allowed the capacity decreases significantly. For WLANs the time between retransmission is much smaller, and the capacity less consequently dependent on the delay requirement (for delay requirements in the range of GSM/EDGE).

5

In the examples above, a capacity gain can thus be achieved by allocating the packets in the access technology that most efficiently handles the packet characteristics (delay and/or error rate requirement) in question.

All these described packet-characteristics can according to the invention be used as selection criteria of access, individual and in combinations, as will be illustrated with the following embodiments.

When multiple associations are maintained, for example by establishing connection paths through more than one access as described in the reference "Simultaneous Access" mentioned above, it will be possible to select on which access each packet shall be sent. The choice is then based on packet-characteristic. The packet characteristic can be extracted from the (IP-)header of the packet or by measuring the packet(s) in the queue.

The splitting points in the multi access system according to the invention comprise some functions that are specific for the invention. In Figure 1 these functions are shown schematically as means performing the method steps. As defined above the splitting points are nodes in the network, such as for example RNC or SGSN and they are also user terminals. The splitting points are nodes where a selection of access needs to be done. They are switching points and direct data to the different accesses. Even if Figure 1 shows all functions as comprised in the splitting point this is not necessary. The functions could be performed some other place in the network and the result telling which access to select could just be retrieved by the splitting point.

In Figure 1 a splitting point 1 is shown comprising a packet queue 3. Data to be transmitted out from the splitting point is queued here and the packets are separated and transmitted one by one. The splitting point 1 comprises further a packet characteristic determining means 5 that is connected to the packet queue 3. The packet characteristic determining means 5 is adapted to determine a packet characteristic for the first packet in the queue. The packet characteristic is in one embodiment of the invention the packet size. The packet size could be extracted from the header of the packet or it could be determined by measuring how big part of the memory the packet occupies. Other characteristics that could be used as selection criteria are as described above the packet inter-arrival-time, PER-, BER- and delay requirements. PER-, BER- and delay requirements can be extracted from the header. Packet inter-arrival-time can be measured at the packet arrival to the queue.

The splitting point 1 further comprises an access selecting means 7 connected to the packet characteristic determining means 5. The access selecting means 7 is adapted to select one of the available accesses depending on the determined packet characteristic that is retrieved from the packet characteristic determining means 5. If for example the packet characteristic is packet size the access selecting means could comprise predefined threshold values for the packet size. Alternatively threshold values could be sent to the splitting point from some other node in the system. The determined packet size is compared with the threshold(s). One access is selected if the packet size is larger than a threshold and another access if it is smaller. If instead packet inter-arrival-time, PER- BER- or delay requirements is used as the packet characteristic other predefined threshold values should be provided in the access selecting means 7. The access selecting means 7 is suitably connected to a load measuring means 9. The load measuring means 9 measures or retrieves a measure from some other place in the system of the load in the different access systems. These load measurements are forwarded to the access selecting means 7 and should be used together with the packet characteristic when the access is selected. For example if the access selecting means comprises threshold values these values can be adjusted depending on the load in the different accesses. If one access is overloaded at the moment then another access

should maybe be selected even if according to the packet characteristic this is less efficient. In one embodiment of the invention the load measurements are performed centrally in the system and furthermore the thresholds are set and adjusted centrally. Information of adjusted thresholds is then continually distributed to the splitting  
5 points.

The access selecting means 7 is further connected to a switching means 11 which is connected to the packet queue 3 and to the different access systems. The access selecting means 7 is adapted to forward instructions to the switching means 11 about which access that should be selected for each packet. The packets are forwarded one  
10 by one through the switching means 11 and they are directed to the selected accesses. The switching means 11 is thus controlled by the access selecting means 7.

According to the invention there could be more than two access systems. In this case the access selecting means 7 comprises suitably more than one threshold. It is further possible that the access selection can be based on more than one packet characteristic.  
15 See for example the third embodiment.

In Figure 2 a flow chart of the inventive steps is shown. The steps are described in order below:

S21: Receiving in a splitting point 1 packet data that should be transmitted out from the splitting point. In the case where the splitting point is in a user terminal  
20 communicating in the multi-access system the data is data the user of the terminal wants to transmit in the system. The data is arranged in packets and the packets are received in a subsequent order in the splitting point.

S23: Determining in the splitting point one or more packet characteristics for the first packet in the packet queue. The packet characteristics could be for example as  
25 described above packet size, inter-arrival-time, PER- or BER-requirements.

S25: Forwarding the determined packet characteristic(s) for the first packet to an access selecting means 7 in the splitting point.

S27: Measuring the load in the different access systems in a load measuring means 9. This step could be performed earlier in the flow or it could also be performed continually.

5 S29: Forwarding said load measure to the access selecting means 7. The load could be reported to the access selecting means 7 whenever there is a change in load or in predefined time intervals or when the load is changed more than a defined amount or passes defined thresholds.

S31: Selecting one of the available accesses, the selection being based on determined packet characteristic or on both load and determined packet characteristic.

10 S33: Forwarding instructions of which access that has been selected to a switching means.

S35: Connecting the packet queue through the switching means to the selected access system.

15 S37: Transmitting the first packet in the packet queue, i.e. the packet whose packet characteristic was determined, through the selected access.

The steps are then repeated for the next packet in the queue and so on.

The inventive steps are here described as being performed in the splitting point. However it would also be possible to perform the steps in another node in the network and retrieve the result in the splitting point.

20 In Figure 3 a flow chart of one embodiment of the invention is shown. In this embodiment the packet characteristic that is determined is the packet size and the access selecting means comprises at least one threshold value with which the packet size should be compared. The steps are described in order below:

25 S45: Determining the packet size of the first packet in the packet queue in the splitting point by reading it from the header of the packet.

S47: Forwarding the determined packet size to the access selecting means.

S49: Measuring the load in the different access systems. This step could be performed anywhere in the network and anywhere in the flow or continually as described above.

S51: Forwarding the measured loads to the access selecting means.

5 S53: Adjusting the at least one threshold in the access selecting means according to the received load measures. For example if one access system is highly loaded the packet size threshold could be adjusted such that fewer packets will be directed to this access system.

S55: Comparing the determined packet size with the at least one threshold.

10 S57: Selecting an access depending on the relation between the packet size and the threshold(s). For example if a packet size is determined to be larger than the threshold value for the packet size one access is selected and if the packet size is determined to be smaller another access is selected.

S59: Forwarding instructions about the selection to the switching means and proceed as described above.

15 More than one threshold could be provided in the access selecting means. Possibly one access is suitable both for very small packets and for very large packets and another access is suitable for the middle sized packets. Furthermore, if there are more than two different access systems more than one threshold is needed.

20 Another example of packet characteristic that could be determined and used for the selection is packet inter-arrival-time. In this case the packet characteristic determining means is adapted to measure the time between packets arriving to the splitting point. This time could then be used when selecting the most suitable access system. This will be described in more detail when the third embodiment is described below.

25 Delay requirements for the packets can also be used for the selection of access system. One access can be relatively more efficient for delay sensitive packets than another.

All the described packet characteristics could also be combined when making the selection.

Five more detailed embodiments are described below.

**First embodiment, WCDMA R99 (DCH) and 802.11b:**

- 5 In a first embodiment of the invention a multi-access system comprising WCDMA (Wideband Code-Division Multiple Access) and WLAN is described. In Figure 4 throughput as a function of packet size for one 802.11b AP (half duplex) and one WCDMA transceiver with DCH (Dedicated CHannel) channels (full duplex) is shown.

10 WCDMA throughput is rather independent of the packet size, at least down to the RLC (Radio Link Control) payload size of 320 bits (40 bytes). WLAN throughput is very dependent on the packet size. The four different transmission rates of WLAN 802.11b are shown separately in the diagram. For the highest WLAN transmission rate (11Mbps) there is a factor of more than 10 between the throughput for 50 byte packets and 1500 byte packets.

- 15 The reason for the packet size dependency in WLAN is the large physical overhead per packet, as described in "On the need for Efficiency in the 802.11 QoS Solution" by M. Sherman. An equally sized overhead is applied on a small 50 byte packet as for a large 1500 byte packet. From this entails that Figure 4 applies not only for a specific packet size but also for an average packet size. For example; to send one 50 byte  
20 packet and one 1500 byte packet two times physical overhead is required, which is the same as for two 775 byte packets.

Assume for example a typical scenario with TCP/IP traffic with 1000 byte forward packets in average and one 50 byte ACK packet for each forward packet. For such loads there is a clear gain in the total multi-access capacity to send the ACK-packets  
25 on WCDMA DCH and the forward packets on 802.11b.

Without any packet size access selection the packet sizes are distributed evenly on both accesses, that is half of the packets are 50 byte and half are 1000 byte resulting in



an average packet size of 525 byte on both WLAN and WCDMA. This will be the case both with a random access selection per packet as well as with strictly load-based access selection. It will also be the case with service-based access selection if the services have the same packet size distributions. The latter allocates the whole service including forward packets and ACK packets to the same access. For an average packet size of 525 byte the 11Mbps throughput is 2.3Mbps and the WCDMA throughput is 2x1 Mbps (full duplex) (WCDMA full duplex has two separate channels, one for up- and one for downlink, each with 1 Mbps) resulting in a total throughput of 4.3Mbps or 2.15Mbps in each direction (with one 802.11b AP and one WCDMA transceiver).

10 With packet size access selection according to the invention all the 50 byte packets are switched to WCDMA leaving only 1000 byte packets in WLAN. This will result in that the WLAN throughput will be increased to 3.2Mbps and the total multi-access throughput to 5.2 Mbps which is a 21% or a 0.9Mbps increase. The 50 byte packets represent only 1/20 (50/1000) of the total load, that is 260kbps. The remaining 15 1740kbps (2Mbps-260kbps) capacity in WCDMA, is utilized by allocating some 1000 byte packets to WCDMA in addition to the 50 byte packets. In this simple scenario with only two packet sizes this means that the threshold will be below 1000 byte until WLAN is fully loaded with 1000 byte packets and then increased to above 1000 byte until WCDMA is fully loaded with 50 byte and 1000 byte packets and then, when 20 there is some free capacity again in WLAN the threshold is decreased again. For a scenario with more continuous packet size distribution a more constant threshold can be found.

For an uneven uplink/downlink load situation the gain can be even larger. The downlink throughput is 1Mbps for a WCDMA transceiver and 2.2Mbps ( $2.3 * 19/20$ ) for a WLAN AP. Assuming only ACK packets uplink there is only 50kbps load on 25 WCDMA uplink. Allocating the WLAN ACK packets to WCDMA then utilizes this spare capacity. The total downlink throughput is then increased from 3.2Mbps to 4.2Mbps which is 31%.

**Second embodiment, WCDMA R5 (HS-DSCH) and 802.11a/g:**

In Figure 5 the packet size impact on performance is shown for 802.11a/g and HS-DSCH (High Speed-Downlink Shared CHannel).

5 The same type of characteristics as for 802.11b and DCH can be seen and the same access selection applies.

In a downlink limited scenario with 54Mbps modulation on 802.11a the gain on downlink throughput by moving the 50 byte ACK-packets to HS-DSCH is 38% or 4.5 Mbps with one AP and one WCDMA transceiver (3.4 Mbps on HS-DSCH and an increase from 8.5 to 13Mbps on WLAN).

10 **Third embodiment, GPRS and 802.11b:**

When packets are to be sent over GPRS a TBF (Temporary Block Flow) is established. This requires signalling over the radio channel that takes time and costs radio resources. A TBF establishment will result in an additional delay of around

15 400ms for downlink and 150ms for uplink depending on standards. This additional delay will be relatively worse for small packets since larger packets have longer transmission delay. The same applies on signalling costs; the transmission of a large packet costs more and the increase in cost for the TBF establishment is relatively less than for a small packet. When a TBF is established it is kept until a predefined time period has elapsed after the last received packet. This TBF release time is a parameter  
20 that is typically set to 1-5 seconds. After this time period a new TBF has to be established when new packets should be transmitted.

WLAN does not have any similar channel establishment. The packet delay is independent of the time since last sent packet.

25 With a packet inter-arrival access selection the number of TBF establishments can be reduced improving both user quality (delay) and capacity (reduced signalling). If a packet is arrived to the splitting point less than the TBF release time since the last packet was sent on the GPRS access it is also sent on the GPRS access. If the packet

inter-arrival-time is longer the selection is based on load. GPRS is still selected if WLAN is highly loaded.

This packet inter-arrival-time selection can preferably be combined with the packet-size selection. If the packet inter-arrival-time is longer than the TBF release time  
5 GPRS still can be selected if the packet is large. That is when the TBF establishment delay and signalling is relatively small compared to the packet transmission time and cost.

Also delay requirement per packet can be taken into account. Even if packet-inter-arrival time has exceeded the TBF release time GPRS can be selected if the delay  
10 requirements can be fulfilled and GPRS is less loaded.

#### **Fourth embodiment, WCDMA DCH and 802.11b case 2:**

WCDMA DCH has as GPRS additional delay depending on packet inter-arrival-time. That depends on the channel switching mechanism. The packet channel data rate is increased (switched up to a higher data rate, lower spreading code) when more data is  
15 transmitted and decreased when less data has been transmitted. This channel switching mechanism has timers and filters to trigger up- and down-switch.

The access selection function between WCDMA DCH and WLAN can be similar to the combined selection described above for GPRS-WLAN. A filter can be applied that aims to follow the channel switching. WCDMA is then selected during longer periods  
20 with a more constant load while WLAN is selected for shorter bursts of data.

#### **Fifth embodiment, Live video streaming over EGPRS and 802.11b:**

A video stream consists of I(ntra)-frames and P(rediction)-frames. P-frames use the preceding image for prediction of the current picture. The P-frames are then more sensitive for packet errors since following P-frames rely on it while I-frames are  
25 independent.

Both 802.11b and EGPRS (Enhanced GPRS) can deliver very low PER with acknowledged mode by retransmitting faulty packets. However EGPRS acknowledge mode entails long delay, which is not desired for live video streaming. The retransmission on WLAN is fast and does not increase the delay significantly.

5 By transmitting the I-packets on EGPRS and the P-packets on WLAN a higher common capacity can be achieved than allocating whole video-streams to EGPRS and WLAN.

The method according to the invention is implemented by means of a computer  
10 program product comprising the software code means for performing the steps of the method. The computer program product is run in a splitting point terminal as defined above positioned in the multi access system. It could also as described above be run in another node in the system, whereby said node forwards information about the access selection to the splitting points. The computer program is loaded directly or from a  
15 computer usable medium, such as a floppy disc, a CD, the Internet etc.

The present invention is not limited to the above-described preferred embodiments. Various alternatives, modifications and equivalents may be used. Therefore, the above embodiments should not be taken as limiting the scope of the invention, which is  
20 defined by the appending claims.

## CLAIMS

1. A method for selecting radio access system in a multi access system handling packet data services where a terminal can communicate with at least two different types of access systems, characterised by the steps of:
- determining (S23) packet characteristics of each packet to be transmitted;
  - selecting (S31) one of the available accesses for the transmission of each packet, the selection being based on the determined packet characteristic for this specific packet; and
  - transmitting (S37) the packet through the selected access.
2. A method according to claim 1, characterised by providing simultaneous association over more than one access in the system by establishing connections prepared for packet transmission.
3. A method according to claim 1 or 2, characterised by the further steps of:
- measuring (S27) the load in the different access systems; and
  - basing the selection (S31) of access on both packet characteristics and load in the access systems.
4. A method according to any one of the preceding claims, characterised in that the determining (S23; S45) of the packet characteristics comprises determining (S45) the packet size for each packet and thus selecting (S31; S57) one of the available access systems based on the packet size of the packet to be transmitted.
5. A method according to claim 4, characterised by
- comparing (S55) the determined packet size with at least one packet size threshold which is defined in the multi access system as a border value of the packet size where a larger packet size suitably is transferred in one access system and a smaller packet size suitably is transferred in another access system for achieving the best transferring efficiency;

- selecting (S57) one of the available accesses according to the relation between the determined packet size for the packet to be transmitted and the at least one packet size threshold.

5 6. A method according to claim 5, characterised by adjusting (S53) the packet size threshold depending on the load in the different access systems.

7. A method according to any one of the claims 1-3, characterised in that the determining (S23) of the packet characteristics comprises determining the packet inter-arrival-time and thus selecting (S31) one of the available access systems based on the packet inter-arrival-time of the packets to be transmitted.

8. A method according to any one of the claims 1-3, characterised in that the determining (S23) of the packet characteristics comprises determining one or more of the PER, Packet Error Rate, requirement, BER, Bit Error Rate, requirement and delay requirement for each packet and thus selecting (S31) one of the available access systems based on the PER-, BER- and/or delay requirements of the packets to be transmitted.

20 9. A multi access system handling packet data services where a terminal can communicate with at least two different types of access systems, characterised in that the system comprises:

- packet characteristic determining means (5) adapted to determine packet characteristics of each data packet to be transmitted in the system;
- 25 - access selecting means (7) connected to the packet characteristic determining means (5) and adapted to select one of the available accesses for the transmission of each packet, the selection being based on the determined packet characteristic for this specific packet.

10. A system according to claim 9, **characterised in that** the system is adapted to provide simultaneous association over more than one access by establishing connections prepared for packet transmission.

5 11. A system according to claim 9 or 10, **characterised in that** it further comprises load measuring means (9) adapted to measure the load in the different access systems; and in that the access selecting means (7) is adapted to base the selection on both packet characteristics and load in the access systems.

10 12. A system according to any one of the claims 9-11, **characterised in that** the packet characteristic determining means (5) is adapted to determine the packet size of each packet to be transmitted and in that the access selecting means (7) is adapted to select one of the available access systems based on the packet size of the packet to be transmitted.

15

13. A system according to claim 12, **characterised in that** the access selecting means (7) comprises comparing means adapted to compare the determined packet size with at least one packet size threshold which is defined in the multi access system as a border value of the packet size where a larger packet size suitably is transferred in one access system and a smaller packet size suitably is transferred in another access system for achieving the best transferring efficiency and in that the access selecting means (7) is adapted to select one of the available accesses according to the relation between the determined packet size of the packet to be transmitted and the at least one threshold.

20

25 14. A system according to claim 13, **characterised in that** the access selecting means (7) is adapted to adjust the packet size threshold depending on the load in the different access systems.

15. A system according to claim 13, **characterised in that** the access selecting means (7) is adapted to receive the packet size threshold and adjustments of said threshold

30

depending on measured loads in the different access systems from a node in the system.

16. A system according to any one of the claims 9-11, characterised in that the  
5 packet characteristic determining means (5) is adapted to determine the packet inter-arrival-time and the access selecting means (7) is adapted to select one of the available access systems based on the packet inter-arrival-time of the packets to be transmitted.

17. A system according to any one of the claims 9-11, characterised in that the  
10- packet characteristic determining means (5) is adapted to determine one or more of the PER, Packet Error Rate, requirement, BER, Bit Error Rate, requirement and delay requirement for each packet and the access selecting means (7) is adapted to select one of the available access systems based on the PER-, BER- or delay requirements of the packets to be transmitted.

15  
18. A system according to any one of the claims 9-17, characterised in that it comprises splitting points that are common to the different access systems and which are adapted to select one of the access systems for outgoing traffic, said splitting points comprising the packet characteristic determining means (5) and the selecting means  
20 (7).

19. A terminal which can communicate with at least two different types of access systems handling packet data services, characterised in that it comprises  
- packet characteristic determining means (5) adapted to determine packet  
25 characteristics of each data packet to be transmitted in the system;  
- access selecting means (7) connected to the packet characteristic determining means (5) and adapted to select one of the available accesses for the transmission of each packet, the selection being based on the determined packet characteristic for this specific packet.



20. A terminal according to claim 19, characterised in that the terminal supports simultaneous association over more than one access by establishing connections prepared for packet transmission.

5 21. A terminal according to claim 19 or 20, characterised in that it further comprises or retrieves information from a load measuring means (9) adapted to measure the load in the different access systems; and in that the access selecting means (7) is adapted to base the selection of access on both packet characteristics and load in the access systems.

10

22. A terminal according to any one of the claims 19-21, characterised in that the packet characteristic determining means (5) is adapted to determine the packet size of each packet to be transmitted and in that the access selecting means (7) is adapted to select one of the available access systems based on the packet size of the packet to be  
15 transmitted.

20

23. A terminal according to claim 22, characterised in that the access selecting means (7) comprises comparing means adapted to compare the determined packet size with at least one packet size threshold which is defined in the multi access system as  
a border value of the packet size where a larger packet size suitably is transferred in one access system and a smaller packet size suitably is transferred in another access system for achieving the best transferring efficiency and in that the access selecting means (7) is adapted to select one of the available accesses according to the relation between the determined packet size of the packet to be transmitted and the at least one  
25 threshold.

30

24. A terminal according to claim 23, characterised in that the access selecting means (7) is adapted to adjust the packet size threshold depending on the load in the different access systems.

25. A terminal according to claim 23, characterised in that the access selecting means (7) is adapted to receive the packet size threshold and adjustments of said threshold depending on measured loads in the different access systems from a node in the system.

5

26. A terminal according to any one of the claims 19-21, characterised in that the packet characteristic determining means (5) is adapted to determine the packet inter-arrival-time and the access selecting means (7) is adapted to select one of the available access systems based on the packet inter-arrival-time of the packets to be transmitted:

10

27. A terminal according to any one of the claims 19-21, characterised in that the packet characteristic determining means (5) is adapted to determine one or more of the PER, Packet Error Rate, requirement, BER, Bit Error Rate, requirement and delay requirement for each packet and the access selecting means (7) is adapted to select one of the available access systems based on the  $\bar{P}\bar{E}\bar{R}$ -,  $\bar{B}\bar{E}\bar{R}$ - and/or delay requirements of the packets to be transmitted.

15

28. A terminal according to any one of the claims 19-27, characterised in that it is a user terminal or another splitting point, i.e. a common node, in the multi access system.

20

29. A computer program product directly loadable into the internal memory of a processing means within a splitting point node or a user terminal communicating in a multi access system or within another node in the system forwarding information about an access selection to the splitting point or user terminal, comprising the software code means for performing the method steps of any one of the claims 1-8.

25

30. A computer program product stored on a computer usable medium, comprising readable program for causing a processing means within a splitting point node or a user terminal communicating in a multi access system or within another node in the

30

system forwarding information about an access selection to the splitting point or user terminal, to control an execution of the method steps of any one of the claims 1-8.

## ABSTRACT

A method for selecting radio access system in a multi access system handling packet data services where a terminal can communicate with at least two different types of access systems.

According to the invention the method comprises the steps of:

- determining (S23) packet characteristics of each packet to be transmitted;
- selecting (S31) one of the available accesses for the transmission of each packet, the selection being based on the determined packet characteristic for this specific packet;
- and
- transmitting (S37) the packet through the selected access.

(Fig. 2)

1/4




Fig. 1

2/4




Fig. 2




Fig. 3

4/4




Fig. 4




Fig. 5



**This Page is Inserted by IFW Indexing and Scanning  
Operations and is not part of the Official Record**

**BEST AVAILABLE IMAGES**

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

- ☐ **BLACK BORDERS**
- ☐ **IMAGE CUT OFF AT TOP, BOTTOM OR SIDES**
- ☐ **FADED TEXT OR DRAWING**
- ☐ **BLURRED OR ILLEGIBLE TEXT OR DRAWING**
- ☐ **SKEWED/SLANTED IMAGES**
- ☐ **COLOR OR BLACK AND WHITE PHOTOGRAPHS**
- ☐ **GRAY SCALE DOCUMENTS**
- ☒ **LINES OR MARKS ON ORIGINAL DOCUMENT**
- ☐ **REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY**
- ☐ **OTHER:** \_\_\_\_\_

**IMAGES ARE BEST AVAILABLE COPY.**

**As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.**